

Park District of Highland Park

2021 Cunniff Park – Backstop Improvements Project

ADDENDUM #1

Friday, February 19, 2021

ISSUED BY:

Michael Evans
Park District of Highland Park
636 Ridge Road
Highland Park, IL 60035

NOTICE TO ALL PROPOSERS:

The attention of all Proposers is called to this Addendum. This Addendum to the 2021 Cunniff Park - Backstop Improvements Project documents is issued to modify, explain or correct the original documents. It is hereby included in and made part of the RFP Contract Documents and Project Manual, whether or not attached to.

All requirements of the original Project Specifications, Scope of Work and Drawings shall remain in force except as amended by this document.

Please see the following changes:

Item # 1 – Chain Link Mesh

- All chain link mesh shall be class 2A fuse bonded two-inch (2”) chain link mesh. The gauge core will remain the same as specified for all locations.

Item # 2 – Height of Players Bench Fencing

- The height of the Player’s Bench Fencing front sections #1 & 2 shall be seven feet (7’). All other dimensions shall remain the same as specified.